

## 19-32 Bid Table

### Rehabilitation of Angleton Drainage Ditch 10 and Oyster Creek

Item No.	Spec No.	Description	Unit	Quantity	Unit Price	Extension
<b>Oyster Creek</b>						
1	2	Clearing West Bank (Sta -0+50 to 2+50)	Ac.	0.46	\$12,100.00	\$5,566.00
2	2	Clearing East Bank South Area to Sta 5+00 Ditch 10	Ac.	0.26	\$12,100.00	\$3,146.00
3	2	Clearing East Bank North Area to Sta 5+00 Ditch 10	Ac.	0.14	\$12,100.00	\$1,694.00
4	5	Fill - West Bank	C.Y.	2,000	\$14.00	\$28,000.00
5	6	Excavation - West Bank	C.Y.	333	\$12.00	\$3,996.00
6	407	PZ-35 Steel Sheet Pile (12' Long. 22.6" Wide)	S.F.	3,684	\$65.00	\$239,460.00
7	432	24" Thick Rock Rip Rap (16" Dia. 250#)	S.Y.	586	\$65.00	\$38,090.00
8	432	6" Thick Bedding Stone (3/4" to 3" Dia. Round)	S.Y.	586	\$55.00	\$32,230.00
9	433	Geotextile Fabric (DMS 6200 Type 2)	S.Y.	672	\$3.00	\$2,016.00
10	210	Seeding and Fertilizing	Ac.	0.86	\$1,800.00	\$1,548.00
<b>Subtotal</b>						<b>\$355,746.00</b>
<b>Ditch 10</b>						
1	2	Clearing - Tree Removal & De-Snagging	Ac.	5.16	\$6,500.00	\$33,540.00
2	7	Fill- Channel Sta 50+00 to Slope Pvg.	C. Y.	367	\$14.00	\$5,138.00
3	7	Fill - Sta 5+00 to 50+00	C. Y.	22,800	\$14.00	\$319,200.00
4	6	Excavation - Sta 5+00 to Sta 50+00	C. Y.	43,433	\$3.00	\$130,299.00
5	432	Concrete Rubble Channel Fill (Sta 51+10)	L. S.	1	\$2,500.00	\$2,500.00
6	432	Concrete Rubble Channel Fill (Sta 5+00)	L. S.	1	\$10,500.00	\$10,500.00
7	407	PZ-35 Steel Sheet Pile (12' Long. 22.6" Wide)	S. F.	672	\$65.00	\$43,680.00
8	210	Seeding and Fertilizing	Ac.	17.25	\$1,800.00	\$31,050.00
<b>Subtotal</b>						<b>\$575,907.00</b>
		<b>Material Testing (Allowance)(15,000)</b> <b>*Not included in total</b>	L.S.	1	15,000	\$15,000.00
<b>Total</b>						\$946,653.00 <del>\$1,522,560.00</del>

**\*BRAZORIA COUNTY COMMENTS:**

In review of the bid table, it has been determined that the bid table formatted the total incorrectly. Bid table should reflect a total amount of \$946,653.00 (including the material testing amount) and not \$1,522,560.00 as shown. The table added the subtotal of \$575,907.00 into the total twice as well as the \$15,000.00 for the allowance.